

TOPIC: Point of Delivery for Electrical Service for Server Farms and Base Area Network & Local Area Network (BAN/LAN) Equipment

ISSUE:

- The Government is required to provide “electric current” to EDS, per paragraph 5.6 of the contract. However, the demarcation point for hand-off of electrical service to EDS for connection to NMCI, as a contractor build-out responsibility, must be determined.

DECISION:

- The point of delivery for electrical service will be either the existing main or secondary power panel, where possible. If additional electrical power capacity is needed and cannot be delivered from existing electrical panels, the Government will install a transformer within 30’ of the building and adjacent to the new server farm where possible and the point of delivery will be at the secondary side of the transformer including the lugs. All routing of power within buildings and from the newly installed transformer pad is the responsibility of the Contractor.

Agreement 26 Oct 03